

WEST BOYLSTON MUNICIPAL LIGHTING PLANT

4 Crescent Street, West Boylston, Massachusetts 01583

Telephone (508) 835-3681

Fax (508) 835-2952

Addendum 1: EV Charging Station Installation Project

Please add the following corrections, clarifications, and questions and answers from today's site visit.

- Pole mounted transformer shall be provided and installed by WBMLP
- Crushed stone, graded size of 1.5" to 2.5", shall cover fully compacted subgrade below foundations and is to be used behind curb for drainage.
- Signage shall be provided and installed by WBMLP
- Correction to drawing E-1. The line and load side conduits and conductors from the weatherhead to disconnect switch on utility pole and from disconnect switch to metering pedestal shall be 3" PVC schedule 40 conduits with (4) 250MCM XHH-2 AL conductors and (1) #4AWG XHHW-2 CU equipment grounding conductor.
- Alternate designs, such as pre-cast concrete pads, are not allowed.
- The deadline for completing construction and installation shall be June 30, 2023.
- Town of West Boylston may waive electrical permit fee, but the cost of inspections shall be paid by contractor.
- 14-day concrete test is not required. Contractor shall furnish 4,500 psi concrete with epoxy coated reinforcement, dowels for long-term exposed-to-weather conditions.
- Compaction testing of soil is not required. Please contact owner and owners' architect to inspect foundation trenching and mounting template installation prior to pouring concrete.
- 50% payment bond shall be required from contractor that is awarded bid.
- Bids can be submitted electronically to jfitch@wbmlp.org as an attachment that will be opened and read at bid deadline. Sealed bids may be mailed or dropped off prior to bid deadline.